

SUMMARY OF WORK

1. DESCRIPTION OF PROJECT

The work consists of furnishing all labor, materials, and equipment necessary to expand the existing cemetery as shown on the plans and as specified herein for use by the Cemetery. Work includes, without limiting the generality thereof:

- Site work to develop lawns for approximately 2,000 burial spaces using full casket interments, cremation graves and a cremation niche structure.
- Provision and installation of new driveways, entry pillars gates, utilities, landscaping, niche feature, water system, walkways, and patios, bar foundations for gravestones.
- Development of equipment building and storage/work area with septic system.

2. LOCATION OF PROJECT

The work to be performed will be at the existing Oak Ridge Cemetery located off Route 134 at Old Chatham Road in Dennis, Massachusetts as shown on the Plans.

3. SCOPE OF WORK

The work under this contract consists of furnishing all necessary labor, materials, and equipment to construct the expansion of the Oak Ridge Cemetery as described in these Specifications, and as shown on the Plans or specified herein.

A. Work includes, without limiting the generality thereof:

- Land survey to stake improvements.
- Erosion control.
- Preparation of an EPA Stormwater NPDES permit under the 2012 Construction General Permit and monitoring/documenting of the site during construction.
- Site clearing.
- Pavement removal where required.
- Tree removal and offsite disposal of stumps and trees/brush/debris.
- Striping existing topsoil, screening, and stockpiling of topsoil for re-use.
- Rough grading and common earthworks.
- Drainage piping, structures (catch basins/ manholes) and recharge system.
- Water service.
- Paved driveways.
- Concrete foundations for future headstones (headstones are NIC).
- Installation of metal grave lot corner markers.
- Niche Feature

- Stone boulders around niche feature
- Concrete walkways, including stamped concrete patio with stone benches.
- Masonry Pillars and Entry Gates.
- Supply and install placement of all landscape materials (plantings).
- Construction of equipment building with septic system and storage yard.
- All clean-up activities.

END OF SECTION